CHECK SITE CONDITIONS:

Ensure this Criteria is met:

PERMITTED


Plant laden up to 30T (10kN/m2) is permitted at the sides & end of the trench. (Recommended 1.00m exclusion zone)



Active principal highways (A Road), residential roads or closed



Medium boundary wall less than 1.00m high and more than 1.20m away from the edge of the excavation.



Length & width of excavation do not exceed maximum dimensions of chosen



Planned excavation does not exceed the length of 12 weeks.

NOT PERMITTED

brace.

Active railways within 1.50m of the edge of the excavation.



Active motorways / trunk roads within 1.50m of the edge of the excavation.




Watercourses (canals, rivers, streams) within the vicinity




Buildings or structures within 1.50m of the edge of the excavation.

CHECK GROUND CONDITIONS:

Ensure the following Criteria is met:







FRAME SELECTION:

Select a set of manhole brace legs which satisfy the dimensions of your excavation. Frames should be supported using a minimum of 2No Standard duty Hanging chins per leg

Type A:



Internal Dimensions	Internal Dimensions	External Dimensions	External Dimensions	SWL
(Min.)	(Max.)	(Min.)	(Max.)	
1.615m	2.715m	1.975m	3.075m	65 kN/m



Type B:



Internal Dimensions	Internal Dimensions	External Dimensions	External Dimensions	SWL
(Min.)	(Max.)	(Min.)	(Max.)	
2.615m	3.715m	2.975m	4.075m	41 kN/m



Type C:



Internal Dimensions	Internal Dimensions	ions External Dimensions External Dimensions		SWL
(Min.)	(Max.)	(Min.)	(Max.)	
3.615m	4.715m	3.975m	5.075m	25 kN/m






Indicates the weight of an individual manhole brace leg. 4No, manhole braces are required to make full frame.




A Competent person (Suitably Qualified & Experienced Person) must assess the ground / site conditions prior to commencement. If the above criteria is not met, this solutions is invalid. In this case; the Temporary works designers - SJG Temporary works Ltd - must be consulted for a site specific design.




Max Type A Brace Dimensions:






Scan to view the Double Acting Manhole Brace User Guide

Max Type B Brace Dimensions:



Max Type C Brace Dimensions:



Residual Risks

Unplanned Excavation (Over-dig) The Client must ensure that excavation is controlled so that excavation levels are not

exceeded. Services:

Care should be taken to prevent damage to existing services. Exposed services should be suitably supported.

Surcharging of Material

The client must ensure the design surcharge of 10 kN/m² is not exceed. The Client is to avoid surcharging the excavation with spoil or other plant/materials.

Edge Protection

It is the clients responsibility to provide adequate

edge protection Access / Egress

The Client is responsible for providing a safe method of access / egress from the excavation.

Assembly & Dismantling of Manhole Brace

It is the responsibility of the Client to produce a method statement for the safe assembly and dismantling of the manhole brace frames.

NOTES:

Drawing to be read in conjunction with SJG site specific calculations.

Prior to construction, the client is responsible for ensuring design complies with their requirements stated in the design brief.

All levels in metres unless noted otherwise. All dimensions in millimetres unless noted otherwise.

Any ground works to be completed by others.

No alterations to the design are to be made without written confirmation form SJG TW Ltd.

This drawing is confidential and exclusive property of the client. No unauthorised use, copy or disclosure is to be made and is to be returned on

All connections to be as per manufacturer's instructions and to be installed by others.

All works to be carried out in accordance with an approved safe system of work (ssow) and risk assessment method statement (rams).

Any 'permits to load' and 'permits to strike' to be issued by a competent person before loading or

11. SJG TW Ltd are not responsible for any localised cracking to the permanent works due to loading or

any workmanship/ quality issues. 12. SJG TW Ltd are not responsible for any remedial works that may be required.

The client is responsible for implementing suitable monitoring and maintenance schemes throughout the duration that the temporary works are in use.

The client is responsible for preparing suitable ground conditions prior to erection

0 30 14,14,14	28/06/18	2			SJG	0
Rev Des Chk App Date Description	Date	ρр	١.	Chk	Des	Rev

Client

PRO SHORE





Standard Detail

Job Title

Drawing Scale: Not to Scale

Generic Excavation Designs

Designer: SJG	Date: 2	28/06/2018
Checker:	Date:	
Approved:	Date:	
Dwg Number:		Rev
PRO/STD/DES/004-01		0